

FIELD DAMAGE REPAIR TECHNICAL DATA SHEET



LOOK BENEATH THE IGNITION-RESISTANT PYROTITE COATING AND YOU'LL FIND THE STRENGTH OF LP[®] OSB.

LP[®] FLAMEBLOCK[®] FIRE-RATED OSB SHEATHING FEATURES A PROPRIETARY NON-COMBUSTIBLE, FIBERGLASS-REINFORCED PYROTITE[®] TREATMENT.

PATCHING AND REPAIR PROCEDURES FOR LP[®] FLAMEBLOCK[®] PANELS

In the event that damage occurs to an LP[®] FlameBlock[®] panel in the field, repairs can be made.

For damaged areas due to overdriving of nails, if the nail is driven past the Pyrotite coating and the OSB is exposed more than 5/8" (the size of a dime) in diameter, the area can be repaired by using a code compliant fire-rated compound or fire-rated caulk.

For damaged areas less than 4 sq. in. in size (approximately the size of a soda can in diameter), the area can be repaired by using a code compliant fire-rated compound or fire-rated caulk. If there is more than one area this size damaged on a panel, this method should only be used if the damaged areas are spaced a minimum of 3 inches apart and should not be used if there is more than a square foot of damaged area present on the panel.

For damaged areas larger than 4 sq. in., the easiest solution is usually to replace the damaged section of panel and add blocking behind the horizontal joints as needed. If this is not feasible, please contact LP Building Products (1-888-820-0325).

For more information about LP FlameBlock Fire-Rated OSB Sheathing, including our Technical Guide, call 1-888-820-0325 or visit LPCorp.com/FlameBlock.



Cal. Prop 65 Warning: Use of this product may result in exposure to wood dust, known to the State of California to cause cancer.

LPCorp.com/FlameBlock
 Phone: 1-888-820-0325
 Email: customer.support@lpcorp.com

For more information about LP FlameBlock Fire-Rated OSB Sheathing, including our Installation Instructions, Safety Data Sheet, and Technical Guide, call 1-888-820-0325 or visit LPCorp.com/FlameBlock