

INSTALLATION QUALITY ASSURANCE MANUAL | AMERICAS

Geotextile products



Contents

1.	Introduction	3
2.	Material	3
3.	Material delivery	3
4.	Site unloading procedures	3
5.	Site handling and storage procedures	3
6.	Ultraviolet light exposure	3
8.	Installation	4
9.	Seaming quality and method	4
Ар	pendix A: Inventory check list	5
Аp	pendix B: Certificate of Acceptance	6

This information is provided for reference purposes only and is not intended as a warranty or guarantee. Solmax assumes no liability in connection with the use of this information. Please check the revision date and refer to our website for the latest updates.

1. INTRODUCTION

This manual provides an overview of the Solmax Installation Quality Assurance procedures consistent with industry accepted practices to ensure that the nonwoven geotextile products installed will best perform for its intended purpose. In addition, all installation work will be performed in strict accordance per the customer's specifications. Please read the procedures below completely before you begin. If you need further clarification, contact the Solmax Engineering Support Staff for assistance. Remember safety first and use safe practices always on every project.

2. MATERIAL

Solmax nonwoven geotextiles are tough and durable materials packaged to withstand normal wear and tear on a typical construction site. However, as with any construction material, all nonwoven geotextiles should be handled with care and stored properly to ensure that the material properties required for a project are retained to serve long-term project needs. In general, Solmax recommends that American Society of Testing and Material (ASTM) standard D 4873 "Standard Guide for Identification, Storage and Handling of Geosynthetic Rolls & Samples" be followed in its entirety. Specific recommendations by Solmax are elaborated in the following sections.

3. MATERIAL DELIVERY

- A. Upon arrival on site, QA personnel will inventory all materials on-site.
- B. Roll numbers of the nonwoven geotextile will be logged on the Inventory Check List (Appendix A) and cross-referenced with the Bill of Lading.
- C. Copies of the Inventory Check List and signed Bill of Lading should be sent to Solmax corporate headquarters while the on-site QA personnel retains the original copies.
- D. Any visible damage to roll materials should be noted on the roll and Inventory Check List.

4. SITE UNLOADING PROCEDURES

- A. A forklift or front end loader fitted with a tapered pole is recommended for loading and unloading nonwoven geotextile rolls.
- B. The pole should be long enough to extend at least 2/3 (10 feet) of the way into the nonwoven geotextile roll core to avoid the possibility of buckling or breaking the core.
- C. Nonwoven geotextile rolls may also be lifted from flatbed trailers using straps hoisted by a crane or loader.
- D. No more than three rolls should be lifted at the same time. For special length rolls, 1,000 feet or longer, each roll should be handled one at a time.

5. SITE HANDLING AND STORAGE PROCEDURES

- A. Nonwoven geotextile rolls should be lifted off of the ground when moving.
- B. Nonwoven geotextile should be deployed as closely as possible to the designated location minimizing dragging against the ground surface.
- C. Operations of heavy construction equipment directly on the nonwoven geotextile should be avoided.
- D. Nonwoven geotextiles should be stored in a flat, dry and well drained area. All sources of contamination, such as oil, grease, soil and aggregate should be separated from the materials.
- E. During on-site storage, nonwoven geotextile rolls should be protected from moisture, sunlight, theft and vandalism.
- F. The protective wrapping should not be removed until the nonwoven geotextile is ready to be installed.
- G. If stored outdoors for long durations, the nonwoven geotextile should be elevated from the ground surface and covered with a tarpaulin or other opaque plastics.

6. ULTRAVIOLET LIGHT EXPOSURE

When left exposed to ultraviolet light, all nonwoven geotextiles slowly degrade, losing strength in the process. It is highly recommended not to expose Solmax nonwoven geotextiles to sunlight prior to installation. Once installed, Solmax geotextiles should be covered with designated overlying material. The nonwoven geotextile should not be left exposed to sunlight for more than 15 days.

7. INSTALLATION

Solmax nonwoven geotextiles should be installed only after the underlying material or subgrade has been properly inspected and approved. The nonwoven geotextiles should be installed to the grade and location specified in project specifications. The project construction quality assurance and construction quality control (CQA/CQC) guidelines must be followed during the installation. An additional important resource for construction guidelines for all geosynthetics is "Technical Guidance Document: Quality Assurance and Quality Control for Waste Containment Facilities" by United States Environmental Protection Agency (Ref. EPA/600/R-93/182).

Solmax recommends minimum geotextile overlap distance from 12 inch to 24 inch, in both machine and transverse directions, unless the project CQA/CQC guidelines specify otherwise.

Care should be taken not to entrap stones or excessive moisture in the nonwoven geotextile during placement. In the presence of wind, all geotextiles should be weighed with temporary ballasting such as sandbags. On slopes, the nonwoven geotextile should be securely anchored and then rolled down the slope in such a manner as indicated by good construction practices and safety considerations.

Prior to the placement of overlying materials, a Certificate of Acceptance (Appendix B) must be signed by a responsible party and an installer's representative. All overlying materials on the nonwoven geotextile should be placed such that:

- · The nonwoven geotextile and the underlying material are not damaged.
- Any movement of the nonwoven geotextile is kept to a minimum.
- · Stresses in the nonwoven geotextile are kept to a minimum.

8. SEAMING QUALITY AND METHOD

Solmax nonwoven geotextiles can be seamed using sewing, hot wedge welding or flame. The quality of a seam depends on seaming equipment, operator experience and site conditions, such as temperature and humidity. Laboratory testing has shown that sewn and hot wedge weld seam provide comparable seam quality, while flame welding is much dependent on operator experience. In general, it is possible to obtain seam efficiency (defined as strength of seam divided by strength of geotextile of up to 80%), if controls are established and implemented. Seaming procedures are typically included in project specifications.

Inventory Check List

Nsed of Roll # Material **Used** Roll# Material QA Technician: Site Manager: **Nsed** Roll # Material **Nsed** Roll # Material Project #:

APPENDIX A: INVENTORY CHECK LIST

APPENDIX B: CERTIFICATE OF ACCEPTANCE

Solmax			
Job:	Project:		
Client:	Bill to:		
Job description:			
% Complete of total job:			
Material	Estimated square (feet / yards)	Final quantity / description	
I, the undersigned, duly representative	of.		
do hereby take over and accept the w			
knowledge the work has been comple		•	
the contract.			
Name:	Signature:	_ Signature:	
Title:	Bill Date:	Bill Date:	
Certificate accepted by representative			
Name:			
Title:	Bill Date:		

About Solmax

Solmax is a world leader in sustainable construction solutions, for civil and environmental infrastructure. Its pioneering products separate, contain, filter, drain and reinforce essential applications in a more sustainable way – making the world a better place. The company was founded in 1981, and has grown through the acquisition of GSE, TenCate Geosynthetics and Propex. It is now the largest geosynthetics company in the world, empowered by more than 2,000 talented people. Solmax is headquartered in the province of Quebec, Canada, with subsidiaries and operations across the globe.

Uncompromised quality

Our products are manufactured to strict international quality standards. All our products are tested and verified at our dedicated and comprehensive laboratories which maintain numerous accreditations. We offer our partners a wide scope of testing according to published standards to ensure products delivered to sites meet specified quality requirements.

Let's build infrastructure better

Solmax is not a design or engineering professional and has not performed any such design services to determine if Solmax's goods comply with any project plans or specifications, or with the application or use of Solmax's goods to any particular system, project, purpose, installation, or specification.